



REFRIGERATED CONTAINER



Installation when the grid is located as a continuation of the container panel (perpendicular to the floor)

1 ► TURNED OFF (b)



a) Container panel.

OFF: Cold equipment must be turned off while filters are installed.



Take out the filters from the plastic sleeve

and use 2 flanges per filter to adjust each

2 ► UNPACK

Intake grids

filter in the grid.

3 ► INSTALLATION

Filters must be placed on the intake grid of the cold equipment, on top of the grid (but not touching the ceiling), avoiding contact between fruit boxes and filters at any time. If 2 filters are installed, the filters should not overlap.

a) Container panel.

b) Grid.









REFRIGERATED CONTAINER



Installation when the grid is located as a continuation of the container panel (perpendicular to the floor)





